GLENVISTA EXT.4

LEGEND

- NEW HYDRANT
- NEW PIPE
- NEW VALVE
- NEW VALVE ON EXISTING PIPE
- NEW HYDRANT ON EXISTING PIPE
- EXISTING VALVE
- EXISTING PIPE
- EXISTING HYDRANT
- END CAP
- TO BE DECOMMISSIONED PIPES
- NEW TEE
- REDUCER
- (1) CONNECTION POINTS
- EXISTING SEWER PIPE

NOTES:

1. ALL NEW FIRE HYDRANTS ARE ABOVE GROUND.
2. uPVC PIPE ARE CLASS 16 HIGH IMPACT PIPES.
3. ALL PIPES TO BE LAID IN ACCORDANCE WITH SANS 1200, LATEST REVISION AND THE REQUIREMENTS OF JOHANNESBURG WATER SOC LTD.
4. CONTRACTOR TO CONFIRM LEVELS OF EXISTING PIPES BEFORE COMMENCING CONSTRUCTION.
5. POSITIONS OF ALL EXISTING SERVICES ARE APPROXIMATED AND MUST BE VERIFIED ON SITE.
6. FOR ALL CONNECTIONS TO EXISTING STEEL AND AC PIPES USE VJ COUPLING OR SIMILAR APPROVED.



DETAIL 1



DETAIL 2

REFER TO DRAWING No:

CONSULTING ENGINEERS CAPEX DESIGN SECTION SWISS HOUSE 7TH FLOOR	DESIGNED	T. NGOBENI — MARCH 2018
	DRAWN	T. NGOBENI — MARCH 2018
	CHECKED	S. NEMUDIVHISO — DATE.....
		SIGNATURE.....
	APPROVED BY:	MJ GUMBO — DATE.....
		SIGNATURE.....
		ECSA REG. No.....

Johannesburg Water

17 HARRISON STREET
MARSHALLTOWN
2107

TEL: (011) 688-1400

FAX: (011) 688-1529

GLENVISTA EXT.4 PHASE 3
WATER PIPE REPLACEMENT
LAYOUT PLAN

SCALE		AMENDMENTS	
AS SHOWN	REV:	DESCRIPTION	DATE:
	0	ISSUED FOR CONSTRUCTION	JAN/2019

DRAWING No.JW13955-GVT-LAY01-W

UR1405 – 0
PROJECT No. REV.

A1 ORIGINAL PAGE SIZE

SHEET 1 OF 1

FILE No.